

Permit: **B3557377** Issue Date: June 07, 2019

Building Permit

Commercial

Pro	perty

Address: 14523 CAROWINDS BLVD Parcel: 20315208 Lot: Block:

Subdivision: Tax Jurisdiction: CHARLOTTE

Site Details

Land Area (sq. ft.): Parking Required: Front Street:

Lot

Corner: N Through: N Irregular: N

Minimum Setbacks (ft.)

Front: Left: Right: Rear:

Project

Project Number: RV-386432-001 Occupancy Type: R2 * RESIDENTIAL - MULTIPLE FA

Project Name: 2019 Carowinds Dormitory Contract Cost: \$54,950 USDC: 214 - Other Non-housekping Shelters (lodge Type of Work: New

Work Details:

New Heated Area: 31335 sq. ft.

Unhtd to Htd:

Renovate Existing:

Deck Area:

Bdrm Add/Upfit:

Owner

Name: Carowinds Address: 14523 Carowinds Blvd

Phone: (803) 415-5867 Charlotte, NC 28273

Trade Details

Electrical

Total Amps: 1,200 Number of Circuits: 389 Connections at 120 Volts: 367 Connections Over 120 Volts: 22

Service Type: New Utility Company: DUKE ENERGY

Mechanical

No. of Gas Connections: 8 No. of Appliances: 0 Utility Company: PIEDMONT NATURAL GAS

Heating/Cooling: Gas Pack

Plumbing

No. of Fixtures: 153 No. of Appliances: 0

Utilities

Water/Well:

Sewer/Septic:

Type of Service: Existing

 Public Meter/Connection
 Private Service

 Individual
 Master
 Individual
 Community

 No
 Yes
 No
 No

 No
 Yes
 No
 No



Permit: **B3557377** Issue Date: June 07, 2019

Building Permit

Commercial

Fees	
------	--

Permit Fee Type:	Construction	Fax Fee:	\$0.00	Fast Track Fee:	\$0.00
*Permit Fee:	\$660.02	Home Owner Recovery Fund:	\$0.00	Fee Adjustment:	\$0.00
Zoning Fee	\$0.00	NESHAP Fee:	\$0.00	Total Fee:	\$660.02
Triple Fee:	\$0.00	Paper Application Fee:	\$0.00	Charge To Acct:	Yes
Fire Damage Fee:	\$0.00	HFR Fee:	\$0.00	Vector OK:	
Cmrcl Surcharge Fee:	\$0.00	Paper Plans Conversion Fee:	\$0.00	NESHAP OK:	

* Permit Fee Calculation is based upon the following costs:

Building Cost less Equipment over \$500K: \$33,000.00 SubPermit Costs: \$21.950.00 Total Equipment Fee \$0.00 Total Cost Calculation: \$54,950.00

Equipment Summary

Total Equipment Costs: \$0.00 \$0.00 Equipment Cost at 100% Equipment Cost at 20% \$0.00

Contractors

SOUTHSIDE CONSTRUCTORS INC **Building Contractor** Contractor ID: X36231

Phone: (704) 825-8881 License #: 45931 Address: PO BOX 19010 Contract Cost: \$33,000 CHARLOTTE, NC 28219

Home Owner: No

Electrical Contractor WALKER ELECTRIC CO INC Contractor ID: X43102 Phone: (803) 324-5220 License #: 27558 Address: P O BOX 386 Contract Cost: \$3,150 RICHBURG, SC 29729 Home Owner: No

Permit Number: E3557401

Mechanical Contractor PERRIGO HTG & A/C CORP Contractor ID: X32326

Phone: License #: (704) 827-6918 16557 P O BOX 365 Address: Contract Cost: \$ 17,200 MOUNT HOLLY, NC 28120 Home Owner: No

Permit Number: M3557402

CAM-FUL INDUSTRIES INC Contractor ID: X37679 **Plumbing Contractor** Phone: (704) 556-0301 License #: 19251 Address: P O BOX 279 Contract Cost: \$ 1,600

PINEVILLE, NC 28134 Home Owner: No

Permit Number: P3557403

Permit Number: B3557377



Permit: **B3557377** Issue Date: June 07, 2019

Building Permit

Commercial

Miscellaneous

Entry Date: 06/7/2019 12:58 pm Entered By: Loos, John

Issue Date: 06/7/2019 Issued By:

Special Inspections: n/a

Lien Agent Number

Agent: Chicago Title Company, LLC 868093

Phone: (888) 690-7384
Fax: (919) 489-5231
Email: support@liensnc.com

Mailing Address: 19 W Hargett ST Unit: 507, Raleigh, North Carolina 27601 Physical Address: 19 W Hargett ST Unit: 507, Raleigh, North Carolina 27601

Agency Holds

As of the time of this permit issuance, the following holds exist on this project:

Agency Phone Number Hold Reason

LUESA Storm Water 9803143206 Elevation Certificate Required

Additional Information: Swim Buffer = 100



Permit: **B3557377** Issue Date: June 07, 2019

Building Permit

Commercial

Remarks

HVAC equipment may encroach into set-back area by 50%.

RTAP is being submitted based on a Meeting May 08, 2019, with Steve Pearson, Tommy Rowland, Allen Croor Vernon representing Mecklenburg County Building Department, along with Joshua Fox Architect, and Randy Ki Construction Co. as the contractor.

Estimated cost changes are stated in previous sheet at \$51,800.00.

Changes as per our meeting:

- 1. In lieu of existing smaller duct shafts at the Second floor only, we are changing this to a larger shaft area to e entire restroom area from the exterior walls to the interior walls and from the 2nd floor precast to the 3rd floor pr the revised plan modifications, existing walls surrounding ductwork will have no rating. We will remove the exist walls at the existing shaft walls, remove the existing wall fire damper installed, install new fire/smoke combinatic within the 8" precast concrete floors with all required connections to the fire alarm system within 6-10ft. (8 locati
- 2. As a request per this meeting noted above due to item #1 above, we will provide full access hollow metal doc at these new areas for full and complete access to all actuators and controls along with full visual inspection for visually inspect. (8 locations). Above doors will be metal stud framed to 6" above ceiling line and will be provide hardi-board for ceramic tile to be re-installed above doors and jambs.
- 3.A couple locations will relocate the wall diffuser and duct to above the restroom ceilings and re-use diffuser in application. All areas have been visually reviewed and we can relocate diffusers within 4ft plus or minus.
- 4. In the utility rooms 237 and 337 next to the elevator shaft we will be accomplishing the same principle as a st entire room, second floor only. We will be removing the existing masonry walls adjacent to the mop sinks full he opened we will form and prep for pouring new 8" concrete slab at this approximate 25"x90" void in the floor. On fire/smoke combination dampers will be installed at this location for same separation from 2nd floor precast to the precast.
- 5. Existing fire rated doors to the restroom and the utility rooms mentioned above will have required accessories to the existing door for smoke requirements. (3 locations)
- 6.Appendix B has been modified to reflect the actual wall requirements as discussed at our meeting.
- 7. Due to removing the masonry wall noted in Item#4 above, we will be relocating the hot and cold water drops the wall being removed to surface mount adjacent too. Both at the second and third floors.
- 8. Sheet M1.01 is only being submitted for clarification, with exhaust fans above the womens water-closets. For No changes occurred.



Permit: **B3557377** Issue Date: June 07, 2019

Building Permit

Commercial

Remarks

Inspection Team

Your project has been assigned to the Commercial Inspection Team. Please visit our website at www.MeckPermit.com to search by address # for the assigned inspectors on your project. For further assistance you can contact the Commercial Management Team:

Manager: Pearson, Steve
Building Supervisor: Croom, Allen K.
Electrical Supervisor: Hartman, Bob
Mechanical Supervisor: DeMaury, Andrew
Plumbing Supervisor: DeMaury, Andrew

To contact your project manager, inspection supervisor or obtain inspection assistance with your project, call 980-314-3134 or 980-314-3140.